



### KEY

**Soft Works**

- Tree-heavy Standard
- Seminative shrub mix planting
- Low ornamental hedge planting
- Ornamental shrub mix planting
- Turf Grass
- Armedly grass seed mix
- Wildflower meadow seed mix

### Plant Schedule

QTY	UNIT CODE	PLANT NAME	SP/CK	FORM	DEPTH/HEIGHT
19	ACE ELS HS	Acer campestre 'Erythra'	R8	STD	12-14cm
3	AMB HL HS	Amelanchier x grandiflora 'Robyn Hill'	R8	STD	12-14cm
6	CR4 PAU HS	Cornus pauciflora 'Paul Scarlet'	R8	STD	12-14cm
4	CR4 STR HS	Cornus monogyna 'Sibirica'	R8	STD	12-14cm
4	MA1 TSC HS	Malus 'Tobolskii'	R8	STD	12-14cm
4	PR4 CHA HS	Prunella celtica 'Chantrelle'	R8	STD	12-14cm
4	SO4 ALC HS	Sorbus aucuparia	R8	STD	12-14cm
238	FR hedge (RB)	Fragaria sylvatica	R8	100-125cm	
1250	FR plants spaced @ 30cm	Fragaria sylvatica	R8	100-125cm	
265	Via Eve Hedge	Viburnum tinus 'Eve Price'	C. 3L	40-50cm	
78	Plants spaced @ 30cm in Single Row	Viburnum tinus 'Eve Price'	C. 3L	40-50cm	

### Plant Mixes

QTY	UNIT	PLANT NAME	SP/CK	SIZE
60	20 No.	Viburnum tinus	C. 3L	40-50cm
50	10 No.	Viburnum opulus	B Trians	60-80cm
50	10 No.	Sambucus nigra	B Trians	60-80cm
150	40 No.	Viburnum tinus	C. 2L	30-40cm
200	50 No.	Berberis canadensis	C. 2L	30-40cm
200	50 No.	Prunella vulgaris	C. 2L	30-40cm
130	35 No.	Cornus monogyna	B Trians	40-50cm
200	50 No.	Viburnum opulus	C. 2L	40-50cm
100	40 No.	Sambucus nigra	C. 2L	30-40cm
100	40 No.	Cornus avellana	C. 2L	40-50cm
100	40 No.	Ribes sanguineum	C. 2L	40-50cm

Client: **Taylor Wimpey**  
Clarendon Road, Hyde

Project: **Soft Landscape Plan 2**

Title: **Soft Landscape Plan 2**

Status: **PLANNING**

Project: 11679 / Drawn: AT / Checked: MT

Scale: 1:100 / Date: 24/11/17 / Approved: MK

Drawing No: UG\_11679\_LAN\_SL2\_DRW\_03 / Revisions: P01

Contractor must check all dimensions from the ground. The planting must be done in accordance with the contract documents and specifications.

Responsibility for the installation of retaining walls, drainage, or other structures is not included in this contract. The contractor must ensure that all structures are built in accordance with the relevant building regulations.

Contractor must ensure that all plants are delivered to site in good condition and are protected during transport.

All plants to be completely hardened off.

Substitutions to be agreed with Landscape Architect.

REV: 24/11/17 PLANNING

REV	DATE	DESCRIPTION	BY	CHKD
01	24/11/17	PLANNING	AT	MT